

# COLD AIR INFLATABLE INSTRUCTIONS - GROUND MOUNT

p: 800.837.6306  
f: 513.733.9500  
425 Elliott Ave., Cincinnati, OH 45215



## What you will need:

- 1 - Inflatable with 8 straps attached
- 1 - Storage bag and ground tarp
- 1 - Extension cord
- 1 - Blower / Inflation fan
- 1 - Inflation tube (either separate or attached)
- 4 - Metal ground stakes

PLEASE SEE PAGE 2 FOR THE  
INSTALLATION GUIDELINES PRIOR TO  
STARTING THE INSTALL!

- Step 1: DO NOT INSTALL IN WINDS OVER 10 MPH**  
Confirm that you have all necessary equipment for installation. Unfold ground tarp to cover installation area. Place the inflatable on the ground tarp and untie rope on bag. Turn bag upside-down so that the opening faces down. Carefully lift the bag away from the inflatable. Spread the inflatable out on the ground tarp.
- Step 2:** Locate metal anchor (d-rings) where tie-down straps will be attached. Most inflatables have four anchor points near the bottom and four near the top. Locate zipper(s) and be certain that they are closed securely.
- Step 3:** Attach one tie-down strap to each anchor point. Insert the loop end of the tie-down strap half way through the d-ring at the anchor point. Insert the other end of the tie-down strap through the exposed end of the loop and pull all the way through.
- Step 4:** Attach the inflation tube to the inflation fan. If you have a separate inflation tube, attach the other end to the inflatable at the large porthole near the bottom. In order to ensure proper operation, the inflation tube must not be twisted between the fan and the inflatable.

- Step 5:** Ground stakes should be installed at a distance from each other equal to the height of the inflatable.  
(example: 20 feet apart for a 20' inflatable)
- Step 6:** Attach the tie down straps from the bottom of the inflatable to the stakes.  
**These straps should be tight!** Loosely attach the tie-down straps to the ground stakes. Make certain that the upper and lower straps from each quadrant of the inflatable are attached to the same ground stake.  
Attach the extension cord to the appropriately powered outlet (110v) and plug inflation fan into the three-outlet power block on the opposite end.
- Step 7:** Turn on the inflatable. Two or more people should hold onto the upper tie-down straps at opposite corners to guide the inflatable upwards. If the straps are tangled or are at improper anchor points, simply turn off the fan, correct the problem and repeat this step.
- Step 8:** Once the inflatable is fully inflated, tighten the upper tie-down straps. It is VERY important that this is done properly to ensure the longevity of the inflatable / install.
- Step 9:** Stand back and inspect the inflatable for straightness and make sure that there is proper clearance from any near objects / obstructions. See completed install pic.

## COMPLETED INSTALL



## REMOVAL:

Open the zipper flap and unzip the zipper approximately 1". Grasp both sides of the opening and slowly spread apart. Pressure from the inside of the inflatable will cause the zipper to open quickly and the inflatable to come down rapidly. Turn off the inflation fan and when applicable remove the tube from inflatable. Detach tie-down straps from stakes. You may leave the tie-down straps attached. **Please make sure that the inflatable is DRY prior to packing into the storage bag!**

# IMPORTANT GUIDELINES - CAI INSTALL

---

- DO NOT repack the inflatable (CAI) while it is wet! This will help prevent mold and mildew from forming on the CAI.
- Deflate the CAI during severe weather conditions. Weather conditions should be monitored by your team the duration of the install. For weather conditions / checks, we have a weather module located on our contractor site, which can be customized for your location(s) - please see the main page of our contractor site.
- If the CAI should happen to blow over, make sure it is not lying on any lighted signage.
- Always keep the CAI at least 2' away from neon signs.
- Please allow adequate room for the CAI. If it is 25' tall, install the CAI in an area that is approximately 25'W x 25'H x 30'H in size.
- Beware of any electrical or power lines in the approximate installation area.
- Always use a tarp under the CAI. This will protect it from dirt / mud or from roof tar.
- If you are anchoring the inflatable to a rooftop fixture, make sure the fixture is firmly bolted to the roof.
- Never tie straps to electrical conduits, vents or gas lines.
- Upon noticing any damage to the CAI, deflate it so that the damaged area does not get worse.
- DO NOT allow the electrical cord to lie in water puddles.
- DO NOT allow the electrical cord to lie on sidewalks or by doorways.

## COMPLETED INSTALL EXAMPLES:



FOR ANY OTHER INSTALLATION  
QUESTIONS, PLEASE DON'T  
HESITATE TO CONTACT YOUR  
ASAP PROJECT MANAGER



p: 800.837.6306  
f: 513.733.9500

425 Elliott Avenue  
Cincinnati, OH 45215

[asapevents.com](http://asapevents.com)